



1. CONCRETE - 6 BAGS CEMENT PER YD CONCRETE,
AIR ENTRAINED CONCRETE - 21500 PSI MIN.
FINAL COMPRESSIVE STRENGTH

2. PLACE DRAIN TILE UNDER FLOOR, 6"
BELOW BOTTOM OF SLAB - DRAIN TILE
TO SUMP PUMP - PLACE TILE 12' O.C.

3. CONTROL JOINTS MAY BE CUT IN SLAB
AT ROOM PARTITIONS

FOUNDATION, WALL & FLOOR SECTION

SCALE 1" = 1'

FOUNDATION, WALL, FLOOR SECTION			
	SCALE	DRAWN BY	DATE
	1" = 1'	R. TRAVIS BARR	
NDSU EXT. AGRIC. ENGINEERING			
DATE	APPROVED BY	DESIGNED BY	
APR 12 72	T.D. TOB-1-8	JSH	