



BILL OF MATERIALS

AMOUNT	DESCRIPTION
1000 SQ. FT.	ASPHALT SHINGLES
1000 SQ. FT.	1/2" EXT. PLYWOOD OR SHEETROCK
4000 SQ. FT.	1/2" EXT. PLYWOOD OR SHEETROCK
95' x 8' SITS.	1 1/2" EXT. C.C. PLYWOOD OR SHEETROCK
51	2 1/2" x 10' FT. RAFTERS
60	2x4 STUDS
1000 SQ. FT.	CEILING PANEL (PANEL X)
3000 SQ. FT.	VAPOR BARRIER (4 mil. poly)
2400 SQ. FT.	1 1/2" BATT INSULATION
60	2x4 x 6 FT. STUDS
300 FT.	2x6 PLATES (TOP & BOTTOM)
20	1/2" ANCHOR BOLTS
1000 SQ. FT.	1/2" EXT. PLYWOOD
1000 SQ. FT.	1/2" EXT. PLYWOOD OR SHEETROCK
16 CU. YDS.	CONCRETE (FOOTINGS & FLOOR)

CROSS SECTION VIEW

HOG FARMWORKING ADDITION TO BARN PREPARED BY: [Blank] CHECKED BY: [Blank]		SCALE: 1/4" = 1'-0" DATE: [Blank]	
APPROVED BY: [Blank] DATE: [Blank]		SHEET: 1 of 1	