



BILL OF MATERIALS

- 25 bags cement.
- 2.5 cu. yds. sand.
- 4.5 cu. yds. gravel or stone.
- 12- 2x6x16'-0" - sills & plates.
- 45- 2x6x12'-0" - studs, joists & ties.
- 19- 2x6x10'-0" - studs.
- 18- 2x4'-16'-0" - rafters, & girts.
- 15- 1x6'-16'-0" - braces, cleats, & removable boards.
- 550 ft. B.M. 1x6" T. #6 - flooring, sheathing & upper doors.
- 1200 lin. ft. - 1x6" - beveled cribbing.
- 17 pieces - 26 ga. corrugated metal, 8'-0" long-roof.
- 80 lin. ft. - 26 ga. metal strip-8" wide-rat band.
- 70 lin. ft. - 26 ga. metal strip-12" wide-rat band.
- 12- 5/8 x 16" anchor bolts, with nuts & washers.
- 39- 6" Tee hinges.
- 13 - Hasps.

Nails, paint, etc. not included in above list.

U.S. DEPARTMENT OF AGRICULTURE	
BUREAU OF AGRICULTURAL ENGINEERING	
DIVISION OF STRUCTURES	
CORN CRIB (700 BU.)	
Drawn by: W.C.F.	CHECKED
Traced by: W.C.E.	SHEET 1 OF 1 SHEET
Approved: _____	SERIAL NO 5533